BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

NAME OF WORK: Improvements to road at Chikkasandra Main Road near Sapthagiri College, Shettyhalli Sub Division, Ward No.12

Sl. No	Description of work	Unit	Qty	Sanctioned Estima Rates	
				In Figures (Rs.)	In Wor (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods Complete as per specifications.	cum	**1094.89**	65.88	Rupees Five a Eighty F Paise C
2	Construction of granular sub-baseby providing close graded material, mixing in a mechanical mix plant at OMC , carriage of mixed Material to work site, spreading in uniform layers with mortor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, Complete as per specifications.	Cum	**469.24**	1060.56	Rupees Thous Sixty and Six Paise
3	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam Specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density Complete as per specifications.	Cum	**625.65**	1121.04	Rupee Thousar Hund Twenty and Fou On
4	Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg/sqm using mechanical means Complete as per specifications.	Sqm	**3128.25**	44.28	Rupee Four Twenty Paise

Signature of the Contractor

Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

KRIDL BBMP RECEIVED Date.....

Executive En

5	Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH Specification clause No. 500.8 complete in all respects Complete as per specifications.	Cum	**76.21**	9631.44	Rupees N Thousand Hundre Thirty O and Forty Paise O
6	Carriage of mixed materials 10 kms for items of Complete as per specifications.	Cum	**76.21**	56.16	Rupees F Six an Sixteen P Only
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Complete as per specifications.	Cum	**1094.89**	72.71	Rupee Seventy and Seve Paise O

Signature of the Contractor

Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Executive Engi
Dasarahalli Divi